



# Scottish Water

Trusted to serve Scotland

## What will this involve - Location

To achieve the aims of the project, new plant and infrastructure will be required, in addition to upgrades and modifications to the existing plant. The map below shows an overview of our proposals.

New MCC Kiosk,  
relocated Mains,  
MCC01, SBR MCC  
Telemetry Outstation

SBR Blowers

New Service Trench

New Chemical  
Dosing, Kiosk,  
emergency shower  
and spill tank

Existing boundary  
fence



Temporary site  
compound

New portable water  
booster

Temporary generator  
and diesel storage  
slab

3 No new sequenced  
batched reactors  
(SBRs)

Proposed boundary  
fence

New sludge holding  
tank

Once the new infrastructure has been built, the redundant plant and equipment will be removed from site.

 [scottishwater.co.uk](http://scottishwater.co.uk)

 [customer.services@scottishwater.co.uk](mailto:customer.services@scottishwater.co.uk)

 0800 0778778

 [facebook.com/scottishwater](https://facebook.com/scottishwater)

 [@scottish\\_water](https://twitter.com/scottish_water)